



I, JAMES E. DAVIS, CERTIFY THAT THIS PLAT WAS PREPARED UNDER MY SUPERVISION AND THAT THE PLAT WAS PREPARED FOR THE PURPOSE OF ACQUISITION AND EASEMENTS ONLY, AND IS NOT INTENDED TO BE A BOUNDARY SURVEY OF PROPERTY SHOWN.



JAMES E. DAVIS, NC PLS L-3747 AUGUST 21, 2013







State of North Carolina
County of Mecklenburg


I, _____, Review Officer of Mecklenburg County, certify that the map or plat to which this certification is affixed meets all statutory requirements for recording.

Review Officer _____ Date _____

LEGEND

-  EXISTING IRON PIN (AS DESCRIBED)
-  BOUNDARY AS SURVEYED
-  BOUNDARY BY DEED OR MAP
-  TEMPORARY CONSTRUCTION EASEMENT (TCE)

LINE TABLE		
LINE	LENGTH	BEARING
L1	3.14'	N 23°45'25" E
L2	25.51'	N 58°48'49" E
L3	10.16'	N 77°33'03" E
L4	24.40'	N 49°46'21" E
L5	1.75'	N 19°33'13" E



- NOTES:
1. TRAVERSE ADJUSTED BY THE LEAST SQUARES ADJUSTMENT METHOD.
 2. ALL DISTANCES ARE HORIZONTAL GROUND DISTANCES.
 3. AREAS DETERMINED BY COORDINATE COMPUTATIONS.
 4. BEARINGS AND DISTANCES SHOWN IN BRACKETS [] ARE BASED ON RECORDED DEED OR MAP INFORMATION.
 5. NC GRID NAD 83 (2011) EPOCH 2010.00 BASIS OF BEARING WAS DERIVED FROM NCGS NETWORK RTK BETWEEN 03-21-2013 AND 03-25-2013 (HORIZONTAL POSITIONAL ACCURACY = 0.08) USING FIXED CONTROL STATION "CONCORD CORS ARP" (N=595,611.29', E=1,533,753.95') AND GEOID MODEL GEOID12A. UNITS ARE US SURVEY FEET.


TOTAL AREA (BY DEED OR MAP): 7,022 SQ. FT.
 AREA IN TEMPORARY CONSTRUCTION EASEMENT: 1,494 SQ. FT.
 AREA REMAINING (BY DEED OR MAP): 7,022 SQ. FT.

PREPARED BY:



LAND DEVELOPMENT SERVICES
 45 SPRING STREET SW CONCORD (704) 786-5404
 CONCORD, NC 28025 FAX (704) 786-7454
 N.C. FIRM LICENSE NO. C-0263

© CESI 2013 CESI JOB NO.: 130505.000

 CHARLOTTE ENGINEERING & PROPERTY MANAGEMENT	
BARTON CREEK GREENWAY	
EASEMENT SURVEY OWNER: MACE MANGOLD	
CHARLOTTE, MECKLENBURG CO., NC	
CHECKED BY: JED SURVEY SUPVR.: JED	
REVISIONS	SHEET 1
SCALE 1" = 30'	OF 1
DRAWN BY: RAP DATE: 08-21-2013	