



CHANGE ORDER

November 17, 2025

**Long Creek Fire Department
6809 Beatties Ford Rd.
Charlotte, NC 28216**

Reference: Removal and replacement of existing unsuitable soil, trash and debris from within proposed building area measuring 40' x 80' to a depth of up to 8'-0'.

OPTION 1

- Undercut and export unsuitable soil under building pad up to 8ft deep.
- Provide and place one layer of geo grid.
- Import and place 2 compacted feet of soil from the Martin Marietta Beatties Ford Rd Quarry.
- Price based on this stone material and soil source only. Price subject to change if other sources are required.

Subtotal.....\$139,904.00
15%GC Fee.....\$ 20,985.00
Total.....\$160,889.00

TERMS: TO BE BILLED MONTHLY

Customer Acceptance of Option 1: Signature: _____

Acceptance Date: _____ Printed Name: _____

OPTION 2

- Undercut and export unsuitable soil under building pad up to 8ft deep.
- Provide and place one layer of geo grid.

- Import and place 8 compacted feet of Stone fill material from the Martian Marietta Beatties Ford Rd Quarry.
- Price based on this stone material source only. Price subject to change if other sources are required.

Subtotal.....\$162,947.00
 15%GC Fee.....\$ 24,442.00
Total.....\$187,389.00

TERMS: TO BE BILLED MONTHLY

Customer Acceptance of Option 2: Signature_____

Acceptance Date:_____ Printed Name:_____

EXCEPT AS NOTED HEREIN, ALL OTHERTERMS AND CONDITIONS NOTED IN BASE CONTRACT, WHICH ARE INCORPORATED HEREIN BY REFERNECE, SHALL REAMIN IN FULL FORCE AND EFFECT.

Contractor:  Date: 11-17-2025